

407-444

CONNECTICUT RIVER BASIN
FARMINGTON, CONNECTICUT
FARMINGTON RESERVOIR DAM
CT 00263

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

The original hardcopy version of this report
contains color photographs and/or drawings.
For additional information on this report
please email



U.S. Army Corps of Engineers
New England District
Email: Library@nae02.usace.army.mil

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

SEPTEMBER, 1980

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00263	2. GOVT ACCESSION NO. ADA144084	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Farmington Reservoir Dam		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE September 1980
		13. NUMBER OF PAGES 55
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Farmington, Connecticut		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Farmington Reservoir Dam is an earth embankment impounding an unnamed tributary to the Pequabuck River and is reported to have been built in 1895. The dam is 760 feet long and 8 ft. wide at the top. In accordance with the Army Corps of Engineers Guidelines, Farmington Reservoir Dam is classified as a high hazard, small size dam. The test flood range is from one-half the PMF. Based upon the visual inspection at the site and past performance, the dam is judged to be in poor condition.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02254

REPLY TO
ATTENTION OF:
NEDED

DEC 19 1980

Honorable Ella T. Grasso
Governor of the State of Connecticut
State Capitol
Hartford, Connecticut 06115

Dear Governor Grasso:


Inclosed is a copy of the Farmington Reservoir Dam (CT-00263) Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Protection, the cooperating agency for the State of Connecticut. In addition, a copy of the report has also been furnished the owner, The Farmington Water Company, Farmington, Conn. 06032.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Protection for your cooperation in carrying out this program.

Sincerely,



WILLIAM E. HODGSON, JR.
Colonel, Corps of Engineers
Acting Division Engineer

Incl
As stated

CONNECTICUT RIVER BASIN
FARMINGTON, CONNECTICUT
FARMINGTON RESERVOIR DAM
CT 00263

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

SEPTEMBER, 1980

BRIEF ASSESSMENT
PHASE I INSPECTION REPORT
NATIONAL PROGRAM OF INSPECTION OF DAMS

Name of Dam:	FARMINGTON RESERVOIR DAM
Inventory Number:	CT 00275
State Located:	CONNECTICUT
County Located:	HARTFORD
Town Located:	FARMINGTON
Stream:	UNNAMED TRIBUTARY TO PEQUABUCK RIVER
Owner:	FARMINGTON WATER CO.
Date of Inspection:	MAY 12, 1980
Inspection Team:	PETER HEYNEN, P.E. MIRON PETROVSKY JAY A. COSTELLO MURALI ATLURU, P.E. JEFFREY BORNE


The Farmington Reservoir Dam is an earth embankment impounding an unnamed tributary to the Pequabuck River and is reported to have been built in 1895. The dam (including spillway) is 760 feet long and eight (8) feet wide at the top. The dam has a maximum impoundment capacity of 64 acre-feet and is about 8 feet in height from the toe of the downstream slope to the top of the dam. The spillway is a 32 foot long, and 2.8 foot high, concrete, ogee shaped weir. There is no information available on outlet pipes.

In accordance with the Army Corps of Engineers Guidelines, Farmington Reservoir Dam is classified as a high hazard, small size dam. The test flood range is from one-half the Probable Maximum Flood ($\frac{1}{2}$ PMF) to the Probable Maximum Flood (PMF). Based upon the potential downstream hazard, the test flood is selected to be equivalent to the $\frac{1}{2}$ PMF. Peak inflow to the impoundment at the test flood is 315 cfs; peak outflow is 250 cfs with the maximum stage in the reservoir at 383.7, or 1.0 foot below the top of the dam. Based on this information the dam is not expected to overtop at the test flood condition. The spillway capacity with the pool at top of dam is estimated to be 525 cfs which is greater than 100% of the routed test flood outflow.



Based upon the visual inspection at the site and past performance, the dam is judged to be in poor condition. There are areas requiring attention, monitoring, and maintenance such as seeps along the toe of the embankment, erosion on the upstream and downstream slopes, location and operation of outlet and inlet structures and valves, and removal of trees.


It is recommended that the owner initiate further studies, to be performed by a registered professional engineer, which would include further inspection to locate inlet structures, valves, conduits, and outlet structures; investigation of seepage and wet areas at the toe of the embankment, removal of trees at the toe of the dam and in the spillway discharge channel, and preparation of "as-built" drawings for future reference. If the low-level outlet is gated on the downstream side of the dam, then measures should be taken to gate it on the upstream side to prevent pressures in the pipe within the embankment.

The above recommendations and further remedial measures presented in Section 7 should be initiated within one year of the owner's receipt of this report.



Peter M. Heynen, P.E.
Project Manager - Geotechnical
Cahn Engineers, Inc.





C. Michael Horton, P.E.
Department Head
Cahn Engineers, Inc.

This Phase I Inspection Report on Farmington Reservoir Dam (CT-00263) has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division



RICHARD DIBUONO, MEMBER
Water Control Branch
Engineering Division



ARAMAST MAHTESIAN, CHAIRMAN
Geotechnical Engineering Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam would necessarily represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

The information contained in this report is based on the limited investigation described above and is not warranted to indicate the actual condition of the dam. The integrity of the dam can only be determined by a means of a monitoring program and/or a detailed physical investigation. The accuracy of available data is assumed where not in obvious conflict with facts observable during the visual inspection.

TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	
Brief Assessment	i, ii
Review Board Signature Page	iii
Preface	iv, v
Table of Contents	vi-viii
Overview Photo	ix
Location Map	x

SECTION 1: PROJECT INFORMATION

1.1	<u>General</u>	1-1
	a. Authority	
	b. Purpose of Inspection Program	
	c. Scope of Inspection Program	
1.2	<u>Description of Project</u>	1-2
	a. Location	
	b. Description of Dam and Appurtenances	
	c. Size Classification	
	d. Hazard Classification	
	e. Ownership	
	f. Operator	
	g. Purpose of Dam	
	h. Design and Construction History	
	i. Normal Operational Procedures	
1.3	<u>Pertinent Data</u>	1-4
	a. Drainage Area	
	b. Discharge at Damsite	
	c. Elevations	
	d. Reservoir	
	e. Storage	
	f. Reservoir Surface	
	g. Dam	
	h. Diversion and Regulatory Tunnel	
	i. Spillway	
	j. Regulating Outlets	

SECTION 2: ENGINEERING DATA

2.1	<u>Design Data</u>	2-1
2.2	<u>Construction Data</u>	2-1

2.3	<u>Operation Data</u>	2-1
2.4	<u>Evaluation of Data</u>	2-1
SECTION 3: VISUAL INSPECTION		
3.1	<u>Findings</u>	3-1
	a. General	
	b. Dam	
	c. Appurtenant Structures	
	d. Reservoir Area	
	e. Downstream Channel	
3.2	<u>Evaluation</u>	3-2
SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES		
4.1	<u>Operational Procedures</u>	4-1
	a. General	
	b. Description of Warning System in Effect	
4.2	<u>Maintenance Procedures</u>	4-1
	a. General	
	b. Operating Facilities	
4.3	<u>Evaluation</u>	4-1
SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES		
5.1	<u>General</u>	5-1
5.2	<u>Design Data</u>	5-1
5.3	<u>Experience Data</u>	5-1
5.4	<u>Test Flood Analysis</u>	5-1
5.5	<u>Dam Failure Analysis</u>	5-2
SECTION 6: EVALUATION OF STRUCTURAL STABILITY		
6.1	<u>Visual Observations</u>	6-1
6.2	<u>Design and Construction Data</u>	6-1
6.3	<u>Post Construction Changes</u>	6-1
6.4	<u>Seismic Stability</u>	6-1

SECTION 7: ASSESSMENT, RECOMMENDATIONS & REMEDIAL
MEASURES

7.1	<u>Dam Assessment</u>	7-1
	a. Condition	
	b. Adequacy of Information	
	c. Urgency	
7.2	<u>Recommendations</u>	7-1
7.3	<u>Remedial Measures</u>	7-2
	a. Operation and Maintenance Procedures	
7.4	<u>Alternatives</u>	7-2

APPENDICES

	<u>Page</u>
APPENDIX A: <u>INSPECTION CHECKLIST</u>	A-1 to A-5
APPENDIX B: <u>ENGINEERING DATA AND CORRESPONDENCE</u>	
Dam Plan, Profile and Sections	Sheet B-1
List of Existing Plans	B-1
Summary of Data and Correspondence	B-2
Data and Correspondence	B-3
APPENDIX C: <u>DETAIL PHOTOGRAPHS</u>	
Photograph Location Plan	Sheet C-1
Photographs	C-1 to C-3
APPENDIX D: <u>HYDRAULIC/HYDROLOGIC COMPUTATIONS</u>	
Drainage Area Map	Sheet D-1
Computations	D-1 to D-10
Preliminary Guidance for Estimating Maximum Probable Discharges	i to viii
APPENDIX E: <u>INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS</u>	E-1



OVERVIEW PHOTO
(May, 1980)

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED DAMS

Farmington Reservoir Dam

TR-Pequabuck River


Farmington

CONNECTICUT

DATE Sept. 1980

CE # 27785KE

PAGE ix



PHASE I INSPECTION REPORT

FARMINGTON RESERVOIR DAM

SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Cahn Engineers, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Cahn Engineers, Inc. under a letter of April 14, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0052 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dam.
3. To update, verify and complete the National Inventory of Dams.

c. Scope of Inspection Program - The scope of this Phase I inspection report includes:

1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.
3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.
4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report passes judgment only on those factors of safety and stability which can be determined by a visual surface examination. The inspection is to identify those visually apparent features of the dam which evidence the need for corrective action and/or further study and investigation.

1.2 DESCRIPTION OF PROJECT

a. Location - The dam is located on an unnamed tributary to the Pequabuck River (Connecticut River Basin) in a suburban area of the town of Farmington, County of Hartford, State of Connecticut. The dam is shown on the New Britain USGS Quadrangle Map having coordinates latitude N41°42.7' and longitude W72°49.6'.

b. Description of Dam and Appurtenances - The dam has a total length of 760 feet, has an "L shaped" configuration and is 7.7 feet in height (See Sheet B-1). The dam is of earth fill construction and is reported by the owner, to have a concrete core. The top of the dam (elevation 384.7) is 2.7 feet above the spillway crest and eight (8) feet wide, with a footpath which extends the length of the dam.

The upstream slope has an inclination of 1 horizontal to 1 vertical above the waterline and flattens out below the water, and is entirely stabilized with weeds and brush (See Photo 1, Appendix C). Riprap extends below elevation 382.7 (approximately 2 feet below the top of slope) and stabilizes the slope below the waterline. The downstream slope has cover similar to the upstream slope with large trees encroaching upon the toe. The slope inclination is 1.5 horizontal to 1 vertical.

The spillway is located at the left end of the dam. It is a 32 foot wide concrete ogee weir (crest elevation of 382.0) and apron structure with concrete training walls (See Photo 3, Sheet B-1). The approach channel is gently sloping and stabilized with riprap. The discharge channel has a hand-laid riprap lining for approximately 25 feet and is unlined thereafter. A small stone wall exists at the left side of the channel, abutting the left training wall and extending 50 feet or more.

At the toe of the dam are two sand filter basins, one dry, one containing water (See Sheet B-1, Overview Photo). The filter to the left side is 34' x 100' and the filter to the right is 74' x 100'. There is a concrete chamber located to the rear of the lefthand filter basin. This chamber is assumed to control flow from the sand filter basins. A channel extends from this concrete chamber towards the spillway discharge channel (See Sheet B-1). The owner stated that there is a 10 or 12 inch blowoff pipe, the valve of which is located at the toe of the dam near the sand filters. The outlet of this pipe could not be located although there is an 8 inch outlet near the smaller sand filter of unknown origin.

The gatehouse is located 20 feet upstream, at the central portion of the dam. It is a 10x10 foot structure with a concrete foundation and brick superstructure. It is accessible by way of a wooden bridge extending from the dam. In the gatehouse, there are 3 manually operated gate stands which are assumed to operate the

sluice gates (only two of the inlets were visible) at the upstream side of the gatehouse foundation. These sluice gates would allow water to enter a wet well from three different levels. Water in the wet well will pass through several screens before release from gatehouse. There are 3 manually operated gate stands which are assumed to operate the outlets (one of which is the gatehouse drain). The exact type, size and location of the outlet pipes and outlet valves is not known. The owner reports that these pipes lead to the filter beds at the toe of the dam.

c. Size Classification - SMALL - The dam is 7.7 feet high and impounds 64 acre-feet of water with the reservoir level at the top of the dam. According to the Recommended Guidelines a dam with this height and maximum impoundment capacity is classified as small in size.

d. Hazard Classification - HIGH - If the dam were breached, there is potential for loss of more than a few lives as well as substantial property damage. At least two houses on Dorset Lane, 2000 ft. downstream of the dam would be flooded with 3.5 and 5 feet of water respectively. The flood would wash out culverts at Dorset Lane and Reservoir Road.

e. Ownership - The Farmington Water Company
105 Main St.
Farmington, Conn. 06032
Mr. Arthur Deming, President
(203) 677-1571
Mr. William Wadsworth, Owner
(203) 677-1870

f. Operator - Same as above.

g. Purpose of Dam - The dam was constructed to impound water for supply to the Town of Farmington. At the present time, the dam has been abandoned as a water supply facility, and has no known functional purpose.

h. Design and Construction History - According to the owner, there are no known engineering plans of the as built structure. The valves, intakes, and treatment facilities were designed by Mr. Hill, a professional engineer from New Haven, Connecticut in 1926. The location of these plans is not known.

According to the owner, the dam was first constructed by Adrian Wadsworth, the owner's father, and founder of the Farmington Water Company in 1895. The impoundment was "spring fed". Additions to the dam were constructed in 1910, 1918, and 1930. In 1930, the dam was raised and a concrete spillway was added.

The dam was operated until 1973 when water quality became unacceptable due to algae problems and inadequate treatment capability. It has not been operated since.

i. Normal Operation Procedures - The reservoir is no longer used as a water supply facility. All valves are reported to be closed. The natural flow leaves the reservoir level at the spillway crest. The water company inspects the area informally approximately one time per month. No formal operation records or lake level readings are known to exist.

1.3 PERTINENT DATA

a. Drainage Area - 0.26 square miles of rolling to mountainous terrain in the Connecticut River Basin, of which less than half is wooded. A housing development is present in the southwestern portion of the watershed.

b. Discharge at Damsite - Normal discharge is over the spillway.

1. Outlet Works (conduits):	Not known
2. Maximum flood at damsite:	Not Known
3. Ungated spillway capacity @ top of dam el. 384.7:	525 cfs
4. Ungated spillway capacity @ test flood el. 383.7:	250 cfs
5. Gated spillway capacity @ normal pool:	N/A
6. Gated spillway capacity @ test flood:	N/A
7. Total spillway capacity @ test flood el. 383.7:	250 cfs
8. Total project discharge @ test flood el. 383.7:	250 cfs

c. Elevations - All elevations are NGVD based on an assumed spillway elevation, See Sheet B-1).

1. Toe of dam:	377+ (varies)
2. Bottom of cutoff:	N/A
3. Maximum tailwater:	N/A
4. Normal pool:	382.0

5. Full flood control pool:	N/A
6. Spillway crest (ungated):	382.0
7. Design surcharge (original design):	Unknown
8. Top of dam:	384.7
9. Test flood surcharge:	383.7
d. <u>Reservoir Length</u> (feet)	
1. Normal pool:	2000 ft.
2. Flood control pool:	N/A
3. Spillway crest pool:	2000 ft.
4. Top of dam:	2100 ft.
5. Test flood pool:	2100 ft.
e. <u>Reservoir Storage</u> (acre-ft.)	
1. Normal pool:	23.5 acre-ft.
2. Flood control pool:	N/A acre-ft.
3. Spillway crest pool:	23.5 acre-ft.
4. Top of dam pool:	64 acre-ft.
5. Test flood pool:	52 acre-ft.
f. <u>Reservoir Surface</u>	
1. Normal pool:	14 acres
2. Flood control pool:	N/A
3. Spillway crest pool:	14 acres
4. Top of dam pool:	16 acres
5. Test flood pool:	15.5 acres
g. <u>Dam</u>	
1. Type:	Earth embankment
2. Length:	760 ft.
3. Height:	7.7 ft.

4. Top width: 8 ft.
5. Side slopes: 1H to 1V Upstream
(above waterline)
1.5H to 1V Downstream
6. Zoning: N/A
7. Impervious core: Unknown (reported to
be concrete by owner)
8. Cutoff: Not Known
9. Grout curtain: Not Known
10. Other: N/A
- h. Diversion and Regulating Tunnel - N/A
- i. Spillway
 1. Type: Concrete, ogee weir
 2. Length of weir: 32 ft.
 3. Crest elevation: 382.0
 4. Gates: N/A
 5. Upstream channel: Riprap
 6. Downstream channel: Riprap
 7. General: N/A
- j. Regulating Outlets - There is no available information
regarding outlets.

SECTION 2: ENGINEERING DATA

2.1 DESIGN DATA

According to the operator, plans of the treatment works including intake structures and valves were prepared in 1926 by an engineer named Hill, from New Haven, Connecticut. These plans have not been located. There are no engineering values, assumptions, test results or calculations available for the original construction or subsequent dam raisings and spillway construction.

Design features are described on the basis of field inspection and information reported by the owner in Section 1.2 (b) of this report.

2.2 CONSTRUCTION DATA

There is no written data available for the original construction of the dam. The owner feels that no plans were prepared for the original dam, but reports that the dam and subsequent additions in 1910, 1918 and 1930 were constructed by the original owner, Mr. Adrian Wadsworth. Likewise, there are no plans for subsequent raisings of the dam.

2.3 OPERATION DATA

The dam is no longer in operation. No formal operational records are known to exist. Lake level readings are not made. The owner provided the following information:

1. The dam has never been overtopped or breached.
2. The reservoir capacity at one time was 7 million gallons.
3. When operating, a daily usage of 30,000 cu. ft. was more than the reservoir could sustain.
4. The dam was last operated in 1973.

2.4 EVALUATION

a. Availability - Existing data was provided by the State of Connecticut and by the owner, who made the premises available for visual inspection.

b. Adequacy - The limited amount of engineering data available is inadequate to perform an in-depth assessment of the dam, therefore, the assessment of this dam must be based on visual inspection, hydraulic computations, hydrologic judgements, and information provided verbally by the owner.

c. Validity - A comparison of the available information and visual observations reveals some discrepancies relative to dam dimensions as recorded in the State of Connecticut's Dam Inventory data sheet.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General - Based upon the visual inspection performed on May 12, 1980 the condition of the dam is poor. Inspection revealed problem areas requiring various levels of maintenance, monitoring and repair. The reservoir was at elevation 382.2 at the time of the inspection.

b. Dam

Top of Dam - The top of the dam is vegetated with grass and brush (Photo 1). A footpath traverses its length. An area of erosion was noted to the right of the gatehouse access bridge (Photo 5).

Upstream Slope - The upstream slope is steep, shows evidence of erosion and needs more riprap protection. A large eroded area extends from the top of dam down the upstream face near (to the right of) the gatehouse (Photo 5). The upstream slope is vegetated with weeds and brush.

Downstream Slope - The downstream slope is being encroached with large trees and heavy brush (Photos 1 and 2). It is irregular and eroded in places. There are areas of stagnant water and small seeps at the toe of the dam (Photo 6).

Spillway - The right training wall has some deterioration at the downstream end, exposing the aggregate (Photo 4). The concrete portion of the left training wall is in good condition, but a small downstream stone wall is broken up. The approach channel is riprapped near the spillway, but has brush and saplings growing farther out in the reservoir along the left side. The discharge channel has a stone bottom, some of which has been washed out.

c. Appurtenant Structures

Intake Structure (Gatehouse) - The exterior foundation and walls were in good condition, however the interior of the gatehouse and the door require maintenance and minor repair.

d. Reservoir Area - The area surrounding the reservoir is rolling, approximately 1/3 wooded, the remainder open land. The watershed is bisected by State Route 6. Reservoir Road approximates the northwest boundary of the watershed.

e. Downstream Channel - The downstream channel is heavily vegetated with overhanging trees and debris in the channel. A single channel flows beneath Reservoir Rd. and discharges to the Pequabuck River 1.5 miles downstream of the dam. A small pond is located approximately 2000 ft. downstream of the dam.

3.2 EVALUATION

Based upon the visual inspection, this dam is assessed as being in poor condition. The following features which could influence the future condition and/or stability of the dam were identified.

1. The erosion area located at the top of the dam and extending down the upstream slope to the right of the gatehouse will erode should the dam become overtopped.
2. Growth of trees and heavy brush on the toe and downstream slope can promote piping and/or seepage by creating flow paths along root systems in the embankment. Large trees, if uprooted may produce depressions in the embankment which may be critical to the stability of the dam.
3. Areas of seepage and standing water at the toe of the slope could result in future stability problems if flows increase without detection.
4. The lack of proper operating and maintenance procedures and information concerning low-level outlets for lowering the reservoir, leaves the dam more susceptible to failure, as well as the owner unprepared, during high flooding conditions.
5. Trees, brush and debris in spillway discharge channel will impede flows during periods of high project discharge.
6. The steep slope and lack of proper protection on the upstream side of the embankment does not provide adequate safety against sloughing and regional slope failure.

SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 OPERATING PROCEDURES

a. General - No formal operation procedures are known to exist. Lake level readings are not taken at the dam. The low-level outlet has not been operated "in some years", as reported by the operator and could not be located during the inspection.

b. Description of Any Warning System in Effect - No formal downstream warning system is known to be in effect.

4.2 MAINTENANCE PROCEDURES

a. General - No formal maintenance procedures are known to exist. The brush is cut from the slopes once a year.

b. Operating Facilities - No maintenance is performed for the operating facilities.

4.3 EVALUATION

The operation and maintenance procedures are poor. A formal program of operation and maintenance procedures should be implemented by the owner, including documentation to provide complete records for future reference. Also, a formal emergency action plan and downstream warning system should be developed and implemented within the time period indicated in Section 7.1c. Remedial operation and maintenance recommendations are presented in Section 7.

SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 GENERAL

The watershed is 0.26 sq. mi. of rolling to mountainous terrain located in the Connecticut River Basin, of which less than half is wooded. A housing development exists in the south-western portion of the watershed and State Route 6 runs through the central portion of the watershed. The maximum impoundment to the top of the dam (El. 384.7 NGVD) is estimated to be 64 ac. ft. and estimated storage below spillway crest is 23.5 ac. ft.

The dam is classified as being small in size and having a high hazard classification.

5.2 DESIGN DATA

No hydraulic or hydrologic design data are available for this dam.

5.3 EXPERIENCE DATA

No information on any serious problem situations arising at the dam or downstream reaches of the dam was found. The maximum previous discharge at this dam is unknown.

5.4 TEST FLOOD ANALYSIS

The test flood for this high hazard, small size dam is in the half Probable Maximum Flood ($\frac{1}{2}$ PMF) to PMF range. Selecting $\frac{1}{2}$ PMF as test flood for this dam based on the size of the dam and involved downstream risk potential, the Corps of Engineers recommended guidelines for drainage areas below 2 sq. mi. (rolling to mountainous terrain) yields a peak inflow of 315 cfs at the test flood for an estimated PMF of 2400 cfs per square mile. The peak outflow is estimated to be 250 cfs with the maximum stage in the reservoir at 383.7 NGVD and maximum surcharge above the spillway crest is estimated to be 1.7 feet. Thus, the dam is not expected to overtop at the selected test flood conditions. The spillway capacity with pool at top of dam is estimated to be 525 cfs which is greater than 100% of the routed test flood outflow. Computations for conditions at the full PMF have also been performed and are given on page D-27 in Appendix D.

5.5 DAM FAILURE ANALYSIS

Utilizing the Corps of Engineers April 1978 "Rule of Thumb Guidance for Estimating Downstream Failure Hydrographs", the peak failure outflow due to dam breach is estimated to be 9200 cfs with an estimated flood depth of 3.5 feet immediately downstream of the dam. The flood routing was performed for peak failure outflow with pool at top of dam. The prefailure flow in the stream is estimated

to be 525 cfs causing depths of 3.1 feet and 1.7 feet in the stream bed at initial and second impact areas respectively. After failure the flood stage is estimated to increase by 4.4 ft. at the initial impact area and by 2.5 ft. at the second impact area thereby resulting in the loss of more than a few lives.

The estimated peak flow rates and peak flood depths at five sections downstream of the dam resulting from a dam failure are:

<u>D/S Section</u> (Ft. from Dam)	<u>Flow</u> (CFS)	<u>Flood Depth</u> (Ft.)	<u>Velocity</u> FPS	<u>Volume</u> <u>Remaining</u> Ac. Ft.
At Dam	9200	3.5	-	64
200	7000	5.4	4.2	49
375	7000	6.8	13	49
1825	6300	7.5	15	44
2125	5600	4.6	8.5	39
2375	4800	4.2	5	33

A flood of this magnitude would flood at least two houses on Dorset Lane housing development 2000+ feet downstream of the dam. The first floor of the house located 4+ feet above the streambed, (east of Dorset Lane adjacent to section DD) would be flooded with 3.5+ feet of water. The velocity of flood water in the vicinity of this house is estimated to be 15 FPS, which could cause severe damage to the structures including the culvert near this house. This potential damage area is designated initial impact area and shown as such on Sheet D-1. Further downstream another house located in between Dorset Lane and a small pond would be flooded with 5+ feet of water (second impact area on Sheet D-1). In addition, Reservoir Road, downstream of the dam would be inundated and the culvert at this road would be damaged. Also, within the 2374 feet reach only 48% of the flood volume is expected to be attenuated (Appendix D-25 & 26).

Based on the hydraulic/hydrologic analysis and the potential for loss of more than a few lives, the dam has a high hazard classification.

SECTION 6: EVALUATION OF STRUCTURAL STABILITY

6.1 VISUAL OBSERVATIONS

The dam is an earth embankment with a 32 foot wide concrete spillway at the left end. The dam is 7.7 feet high and 8 feet wide at the top. The upstream slope is 1H to 1V above waterline and slopes out below the waterline. The downstream slope is 1.5H to 1V. The dam is reported to have a concrete core but no information could be found to support this. The whole embankment has a weed and brush cover. Small seeps and wet areas were noted at the toe of the dam. The slopes are quite irregular with a large erosion area (from trespassing) on the upstream slope just right of the gatehouse. The low-level outlet could not be located during the inspection.

Recommendations addressing these items and other remedial measures are presented in Section 7.

6.2 DESIGN AND CONSTRUCTION DATA

No information is available.

6.3 POST CONSTRUCTION CHANGES

Post construction changes include lengthening the dam through the years between 1910 and 1930, raising the embankment 2-3 feet and adding the concrete spillway in 1930.

6.4 SEISMIC STABILITY

The dam is in Seismic Zone 1, and according to the Army Corps of Engineers Recommended guidelines, need not be evaluated for seismic stability.

SECTION 7: ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Condition - Based upon the visual inspection of the site and past performance, the dam appears to be in poor condition. There are a number of areas of concern which require maintenance, repair and monitoring. These include seeps at the toe, erosion areas, woody vegetation on the downstream slope, and the lack of information on the outlet location and operation.

Based upon "Preliminary Guidance for Estimating Maximum Probable Discharge" dated March, 1978 and hydraulic/hydrologic computations, peak inflow to the reservoir at the $\frac{1}{2}$ PMF is 315 cubic feet per second; peak outflow is 250 cubic feet per second with the dam retaining 1.0 feet of freeboard. The spillway capacity to the top of dam is 525 cubic feet per second, which is greater than 100% of the routed test flood outflow.

b. Adequacy of Information - The information available is such that an assessment of the condition and stability of the dam must be based solely on visual inspection, past performance of the dam, and sound engineering judgement.

c. Urgency - It is recommended that the measures presented in Section 7.2 and 7.3 be implemented within 1 year of the owner's receipt of this report.

7.2 RECOMMENDATIONS

It is recommended that further studies be made by a registered professional engineer qualified in dam design and inspection pertaining to the following:

1. The origin and significance of seepage and wet areas located at the toe of the embankment.
2. Development of a program for monitoring seepage along the toe of the dam.
3. The low-level outlet should be located and inspected. This should include its operation and a check of the outlet channel. If the outlet valve is located on the downstream slope, measures should be taken to gate the outlet on the upstream side of the dam so as to eliminate pressures in the pipe within the embankment.
4. The gatehouse should be inspected to check the exact location and function of valves, inlets and conduits to determine their use as related to the filter basins or low-level outlet.
5. Preparation of "as built" drawings for future reference.

6. Large trees encroaching upon the downstream slope should be removed, backfilled and proper slope protection placed.
7. The upstream slope should be graded to a slope of 2 horizontal to 1 vertical or flatter and slope protection placed to well above the normal waterline.

7.3 REMEDIAL MEASURES

a. Operation and Maintenance Procedures - The following measures should be undertaken within the time period indicated in Section 7.1c, and continued on a regular basis.

1. Round-the-clock surveillance should be provided by the owner during periods of heavy precipitation and high project discharge. The owner should develop and implement an emergency action plan and downstream warning system in case of emergencies at the dam.
2. A formal program of operation and maintenance procedures should be instituted and fully documented to provide accurate records for future reference. As part of the maintenance procedures, the owner or owner representative should perform documented monthly inspections.
3. A comprehensive program of inspection by a registered professional engineer qualified in dam design and inspection should be instituted on a biennial basis.
4. Erosion from trespassing on the slopes and top of dam should be filled and proper protection placed.
5. All trees, brush and debris should be removed from the spillway and along the spillway discharge channel to Reservoir Road.
6. Small trees and sumac on the slopes should be removed.
7. The gatehouse should be restored to a more accessible condition including repairs to the access ramp.
8. Deteriorated concrete at the spillway right training wall should be repaired.

7.4 ALTERNATIVES

- 1) Drain the reservoir and remove the dam.

APPENDIX A
INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST

PARTY ORGANIZATION

PROJECT Farmington Reservoir Dam

DATE: May 12, 1980

TIME: 11:00 AM - 12:30 PM

WEATHER: Cloudy - 60°F

W.S. ELEV. 382.2 U.S.

U.S.

PARTY:

INITIALS:

DISCIPLINE:

1. <u>Peter M. Heynen</u>	<u>PMH</u>	<u>Cahn-Geotechnical</u>
2. <u>Miron Petrovsky</u>	<u>MP</u>	<u>Cahn-Geotechnical</u>
3. <u>Murali Atluru</u>	<u>MA</u>	<u>DTC-Hydrologic</u>
4. <u>Jay A. Costello</u>	<u>JAC</u>	<u>Cahn-Geotechnical</u>
5. <u>Jeffrey O. Borne</u>	<u>JOB</u>	<u>Cahn-Geotechnical</u>
6. <u>Tim K. Kavanaugh</u>	<u>TK</u>	<u>Cahn-Survey</u>

PROJECT FEATURE

INSPECTED BY

REMARKS

1. <u>Dam Embankment</u>	<u>PMH, MP, JAC, MA, JOB, TK</u>	<u>A-2</u>
2. <u>Spillway</u>	<u>PMH, MP, JAC, MA, TK</u>	<u>A-3</u>
3. _____	_____	_____
4. _____	_____	_____
5. _____	_____	_____
6. _____	_____	_____
7. _____	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____
11. _____	_____	_____
12. _____	_____	_____

PERIODIC INSPECTION CHECK LIST

Page A-2PROJECT Farmington Reservoir DamDATE May 12, 1980PROJECT FEATURE EmbankmentBY JAC, PMH, MP, MA,
JOB, TK

AREA EVALUATED		CONDITION
<u>DAM EMBANKMENT</u> Crest Elevation Current Pool Elevation Maximum Impoundment to Date Surface Cracks Pavement Condition Movement or Settlement of Crest Lateral Movement Vertical Alignment Horizontal Alignment Condition at Abutment and at Concrete Structures Indications of Movement of Structural Items on Slopes Trespassing on Slopes Sloughing or Erosion of Slopes or Abutments Rock Slope Protection-Riprap Failures Unusual Movement or Cracking at or Near Toes Unusual Embankment or Downstream Seepage Piping or Boils Foundation Drainage Features Toe Drains Instrumentation System		 381.7 382.2 Unknown None observed N/A None observed } Appears good } None observed Footpath along crest Slope erosion in area of gatehouse ramp Some displacement None observed Some seepage and wet areas along toe } None observed

A-2

PERIODIC INSPECTION CHECK LIST

Page A-3

PROJECT Farmington Reservoir Dam


DATE May 12, 1980

PROJECT FEATURE Spillway

BY PMH, JAC, MBMA, TK

AREA EVALUATED	CONDITION
<u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a) <u>Approach Channel</u>	
General Condition	Riprap appears good, brush & small trees growing in channel
Loose Rock Overhanging Channel	N/A
Trees Overhanging Channel	
Floor of Approach Channel	Good
b) <u>Weir and Training Walls</u>	
General Condition of Concrete	Some slight spalling, area of cracking & deterioration on right wall
Rust or Staining	None observed
Spalling	Right training wall
Any Visible Reinforcing	
Any Seepage or Efflorescence	None observed
Drain Holes	
c) <u>Discharge Channel</u>	
General Condition	Poor
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	Yes
Floor of Channel	Loose riprap, debris, boulders
Other Obstructions	N/A

APPENDIX B
ENGINEERING DATA AND CORRESPONDENCE




NOTES:

1. THIS PLAN WAS COMPILED FROM CAHN ENGINEERS INSPECTION OF THE DAM DATED JUNE 2, 1980. DIMENSIONS SHOWN ARE APPROXIMATE. NOT ALL TOPOGRAPHIC AND OR STRUCTURAL FEATURES ARE NECESSARILY IDENTIFIED.
2. NO ELEVATIONS WERE AVAILABLE FOR THE DAM THEREFORE THE WATER SURFACE ELEVATION OF 382.0 FOR THE RESERVOIR SHOWN ON THE 1972 U.S.G.S. NEW BRITAIN QUADRANGLE MAP WAS ASSUMED TO BE THE N.G.V.D. ELEVATION OF THE SPILLWAY CREST. ALL OTHER ELEVATIONS SHOWN ARE REFERENCED TO THE ASSUMED SPILLWAY CREST ELEVATION.



SECTION B-B

3 0 3 6



SECTION A-A

3 0 3 6

CAHN ENGINEERS INC. WALLINGFORD, CONNECTICUT ENGINEER	U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.			
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS PLAN & SECTIONS FARMINGTON RESERVOIR DAM				
TR- PEQUABUCK RIVER FARMINGTON, CONNECTICUT				
DRAWN BY H. Norman	CHECKED BY JAC	APPROVED BY AM	SCALE: AS NOTED DATE: SEPT. 1980	SHEET B-1

FARMINGTON RESERVOIR DAM

EXISTING PLANS

None Available

SUMMARY OF DATA AND CORRESPONDENCE

<u>DATE</u>	<u>TO</u>	<u>FROM</u>	<u>SUBJECT</u>	<u>PAGE</u>
No Date	File	State Board of the Supervision of Dams	Inventory Data	B-3

No. F-1

WATER RESOURCES COMMISSION
SUPERVISION OF DAMS
INVENTORY DATA

Inventoried
By T.C.

Long 72-49.6

Date 6-13 KR

Lat 41-42.7

Name of Dam or Pond Farmington Reservoir

Code No. F 0.75 U 1.0

Nearest Street Location Reservoir Road

Town Farmington

#2

Pumping House

U.S.G.S. Quad. New Britain

Name of Stream Trib of Pequabuck River

Owner Town of Farmington

Address _____

ok
6/77

Farm Water Co
1895 - 1910 - 1929. (677-1870)

Pond Used For Public Water Supply DA 0.35 in

Dimensions of Pond: Width _____ Length _____ Area 13.8

Total Length of Dam 250' 760' Length of Spillway 32'

Location of Spillway _____

Height of Pond Above Stream Bed 15'

Height of Embankment Above Spillway 3.6'

Type of Spillway Construction No Spillway, drawdown Pipe

Type of Dike Construction Earth

Downstream Conditions Road 200' below - Houses


1/2 mile below

Summary of File Data _____

Remarks _____

APPENDIX C
DETAIL PHOTOGRAPHS

— FARMINGTON RESERVOIR —



2
← PHOTO NUMBER AND DIRECTION

PHOTO	LOCATION	PLAN
FARMINGTON RESERVOIR DAM		
SHEET C-1		



Photo 1 - Upstream slope from gate house (May, 1980)



Photo 2 - Top of dam and downstream slope from spillway. Gate house in background, (May, 1980).

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Farmington Reservoir Dam
TR-Pequabuck River
Farmington, CT
CE # 27785KE
DATE Sept. 1980 PAGE C-1



Photo 3 - Ogée shaped concrete weir at left end of dam,
(May, 1980).



Photo 4 - Deterioration of concrete at right spillway wall,
(May, 1980).

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Farmington Reservoir Dam
TR-Pequabuck River
Farmington, CT
CE# 27 785 KE
DATE Sept. 1980 PAGE C-2



Photo 5 - Erosion on upstream slope just to the right of the gate house, (May, 1980).



Photo 6 - Wet area with stagnant pool along toe of dam, (May, 1980).

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.


CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Farmington Reservoir Dam
TR-Pequabuck River
Farmington, CT

CE# 27 785 KE
DATE Sept. 1980 PAGE C-3

APPENDIX D
HYDRAULICS/HYDROLOGIC COMPUTATIONS



CAHN ENGINEERS INC. WALLINGFORD CONNECTICUT ENGINEER		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS DRAINAGE AREA MAP			
FARMINGTON RESERVOIR DAM			
TR-PEQUABUCK RIVER		FARMINGTON, CONNECTICUT	
DWN. BY	CKD. BY	APP. BY	SCALE: 1"=2000
M. Norman	JHC	JHC	DATE: SEPT. 1980
			SHEET D-1

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 1 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/16/80
FARMINGTON RES. DAM CHECKED BY EL DATE 7/17/80

PERFORMANCE AT PEAK FLOOD CONDITIONSPROBABLE MAXIMUM FLOOD (PMF) DETERMINATION

DRAINAGE AREA - 0.26 SQ. MI. PLANIMETERED FROM USGS MAP.

WATERSHED CLASSIFICATION - "ROLLING" TO "MOUNTAINOUS"
BASED ON USGS MAP AND SITE VISIT.

PMF PEAK INFLOW

FOR DRAINAGE AREA < 2 SQ. MI. WITH ROLLING TO MOUNTAINOUS TERRAIN, THE CORPS OF ENGINEERS RECOMMENDS CSM VALUE TO BE IN THE 2000 TO 2500 CFS/SQ. MI. RANGE.

ACCORDINGLY, FOR THE FARMINGTON RESERVOIR WATERSHED, PEAK FLOW RATE = 2400 CFS/SQ. MI. IS SELECTED.

$$\text{PMF PEAK INFLOW} = 2400 \times 0.26 = 625 \text{ CFS}$$

$$\frac{1}{2} \text{ PMF PEAK INFLOW} \approx 315 \text{ CFS}$$

SIZE CLASSIFICATION

FOR THE PURPOSE OF DETERMINING PROJECT SIZE, THE MAXIMUM STORAGE ELEVATION IS CONSIDERED EQUAL TO THE TOP OF DAM.

TOP OF DAM

$$= \text{EL. } 384.7^* \text{ NGVD}$$

HEIGHT OF DAM

$$= \text{EL. } 384.7 - \text{EL. } 377.0 \text{ (TOP OF THE DAM)} \\ = 7.7 \text{ FT}$$

* THE U.S. ELEVATION 382 MSL ON THE NEWBRITAIN, CT. QUADRANGLE SHEET (REV. 1972) IS ASSUMED TO BE THE SPILLWAY CREST ELEV. ON NATIONAL GEODETIC VERTICAL DATUM (NGVD). ALL OTHER ELEVATIONS ARE REFERENCED TO THIS ASSUMED ELEV. AND ARE OBTAINED BASED UPON INFORMATION FURNISHED BY CAHN ENGINEERS.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 2 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/16/80
FARMINGTON RES. DAM CHECKED BY Ed DATE 7/17/80

PLANIMETERING FROM USGS MAP FOR RESERVOIR SURFACE AREAS
 AT EL. 382 (SPILLWAY CREST) = 14 ACRES
 AT EL. 390 = 20 ACRES
 AT EL. 400 = 28 ACRES


A STAGE-RESERVOIR AREA CURVE IS PLOTTED (SHEET 3)
 FROM THIS CURVE, RESERVOIR AREA AT TOP OF DAM = 16 ACRES
 AVERAGE RESERVOIR AREA BETWEEN SPILLWAY CREST AND
 TOP OF DAM = 15 ACRES
 STORAGE BETWEEN SPILLWAY CREST & TOP OF DAM
 $= 2.7 \times 15 = 40.5 \text{ AC.FT.}$

ESTIMATED STORAGE BELOW SPILLWAY CREST = $\frac{1}{3}bh$
 $= \frac{1}{3} \times 14 \times 5 = 23.5 \text{ AC.FT.}$
 ($b = 14 \text{ AC.}$ $h = \text{EL. } 382 - \text{EL. } 377 = 5$)

∴ MAXIMUM IMPOUNDMENT TO TOP OF DAM
 $= 40.5 + 23.5 = 64 \text{ AC.FT.}$

A STAGE-STORAGE CURVE IS PLOTTED ON SHEET 3
 THUS, ACCORDING TO CORPS OF ENGINEERS GUIDA-
 LINES TABLE 1, THE FARMINGTON RESERVOIR DAM
 IS CLASSIFIED AS SMALL BASED UPON THE STORAGE
 CAPACITY OF 64 AC.FT. (< 1000 AND ≥ 50) AND
 HEIGHT OF THE DAM IS ONLY 7.7'.

D-3



SHEET 3 OF 27
 DATE 7/14/80
 BY 66 7/17/80

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 4 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/18/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/19/80
REV. MA 9/12/80

HAZARD POTENTIAL - HIGH HAZARD POTENTIAL
DAM BASED ON DAM BREACH ANALYSIS AND
RELATIVE LOCATIONS OF HOUSES AND OTHER STRUCTURES.

A DETAILED DISCUSSION OF FAILURE HAZARD POTENTIAL
IS INCLUDED AT THE END OF BREACH ANALYSIS SECTION
OF APPENDIX - D.

SELECTION OF TEST FLOOD -
FOR THE SMALL SIZE AND HIGH HAZARD POTENTIAL
CLASSIFICATION, TABLE 3 OF CORPS OF ENGINEERS
RECOMMENDED GUIDELINES. THE TEST FLOOD COULD BE
IN THE $\frac{1}{2}$ PMF TO PMF RANGE. BECAUSE OF THE SMALL
SIZE OF THE PROJECT (THE DAM IS ONLY 7.7 FT
HIGH),


A TEST FLOOD IN THE LOWER RANGE IS
SELECTED. TEST FLOOD = $\frac{1}{2}$ PMF

TEST FLOOD PEAK INFLOW = 315 CFS


NOTE 1 SURCHARGE STORAGE ROUTING IS ALSO
PERFORMED FOR PMF PEAK INFLOW.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 5 OF 27
NEW ENGLAND DIVISION COMPUTED BY MMB DATE 7/18/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/19/80

COMPOSITE DISCHARGE RATING CURVE



POTENTIAL OVERFLOW PROFILE (BASED ON CF FIELD INFORMATION)



SPILLWAY -

$$Q_1 = CLH^{3/2}$$

$$= 3.7 \times 32 \times H^{3/2}$$

$$= 118.4 H^{3/2}$$

FOR SPILLWAY WITH A ROUNDED
CRESTED SHAPE $C = 3.7$ ASSUMED.
(REF: HANDBOOK OF APPLIED
HYDROLOGY BY VEN TE CHOW CHAPTER 7)

DAM -

$$Q_2 = CLH^{3/2}$$


$$= 2038 H^{3/2}$$

$C = 2.8$ ASSUMED (BRUSH)
 $L = 728'$
CR. EL. 384.7

LEFT EMBANKMENT -

$$Q_3 = \frac{2}{5} CL^{5/2} (h_b - h_a)^{5/2}$$

$$= 8.8 h_b^{5/2} \text{ FOR } h_a = 0 \text{ UP TO EL. 390.6}$$



RIGHT EMBANKMENT - DISCHARGE COMPUTED SIMILAR TO LEFT EMBANKMENT.

* USGS RECOMMENDED FORMULA FOR MORE PRECISE DISCHARGE OVER
INCLINED DAM/EMBANKMENT CREST (REF: MEASUREMENT OF PEAK
DISCHARGES AT DAM BY INDIRECT METHODS, USGS BOOK 3, CHAPTER
A-5, PAGE 3-4, 1968)


PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 6 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/18/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/19/80

TABULATION OF DISCHARGE RATES (CFS)

	ELVN.	SPILLWAY Q ₁	DAMQ.	TOTAL Q
SPILLWAY →	382	0	0	0
	382.5	42	0	42
	383	118	0	118
	383.5	218	0	218
TEST FLOOD = 1/2 PMF →	383.65	250	0	250
	384	335	0	335
PMF @ TOD →	384.7	525	0	525
	384.8	555	64	619
	384.9	585	182	767

NOTE: FOR THE POOL ELEVATIONS ABOVE THE TOP OF DAM IN THE TABLE, Q₃ AND Q₄ FOR EMBANKMENTS ARE NEGLIGIBLE. ALSO, LOW-LEVEL OUTLET COULD NOT BE FOUND AND THEREFORE IS NOT INCLUDED IN THIS ANALYSIS.

DISCHARGE RATING CURVES FOR TOTAL Q (COMPOSITE) AND SPILLWAY ARE SHOWN ON SHEET 7.



PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 8 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/18/80
FARMINGTON RES. DAM CHECKED BY Eb DATE 7/19/80

DETERMINATION OF PEAK OUTFLOW—

BY USING THE CORPS OF ENGINEERS "SURCHARGE
STORAGE ROUTING" ALTERNATE METHOD:

FOR 315 CFS ($\frac{1}{2}$ PMF) THE DISCHARGE RATING CURVE
 GIVES ELVN = 383.92
 FROM STAGE-STORAGE CURVE FOR THIS ELVN STORAGE = 30 AC·FT

$$STOR_i = \frac{30 \times 12}{0.26 \times 640} = 2.16'' \text{ RUN-OFF}$$

$$Q_{P_i} = Q_P \left(1 - \frac{STOR_i}{9.5} \right)$$

① STOR _i INCHES	② $\left(1 - \frac{STOR_i}{9.5} \right)$	③ STOR _i AC·FT $\frac{12}{0.26 \times 640}$	④ Q _{P_i} CFS ② × 315	⑤ ELVN FROM STORAGE CURVE USING ③
1.5	0.84	20.8	265	383.25
1.75	0.82	24.3	258	383.5
2.16	0.77	30	242	383.92

COLUMNS ④ ③ ⑤ ARE PLOTTED ON DISCHARGE RATING
CURVE AND

$\frac{1}{2}$ PMF PEAK OUTFLOW Q = 250 CFS
 MAXIMUM STAGE = 383.65 NGVD
 TOP OF DAM = 384.7 NGVD

∴ THE DAM IS NOT EXPECTED TO BE OVERTOPPED.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 9 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/18/80
FARMINGTON RES. DAM CHECKED BY CB DATE 7/19/80

THE ROUTING IS ALSO DONE FOR INFLOW OF 625 CFS -
 BY USING THE CORPS OF ENGINEERS "SURCHARGE STORAGE
 ROUTING" ALTERNATE METHOD:

FOR 625 CFS (PMF) THE DISCHARGE RATING CURVE GIVES
 ELVN = 384.81

AND FROM STAGE-STORAGE CURVE FOR THIS ELVN, STORAGE
 = 44 AC.FT.

$$STOR_i = \frac{44 \times 12}{0.26 \times 640} = 3.17'' \text{ RUN OFF.}$$

$$Q_{P_i} = Q_{P_i} \left(1 - \frac{STOR_i}{19}\right)$$

① STOR _i INCHES	② $\left(1 - \frac{STOR_i}{19}\right)$	③ STOR _i AC.FT ① $\times \frac{0.26 \times 640}{12}$	④ Q _{P_i} CFS ② $\times 625$	⑤ ELVN FROM STORAGE CURVE USING ③
2.50	0.87	34.7	544	384.2
2.75	0.86	38.1	538	384.3
3.00	0.84	41.6	525	384.7
3.17	0.83	44	519	384.81

COLUMNS ④ & ⑤ ARE PLOTTED ON DISCHARGE RATING
 CURVE AND

PEAK OUTFLOW Q = 525 CFS.

MAXIMUM STAGE = 384.7 NGVD

∴ THE DAM IS NOT EXPECTED TO OVERTOP.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 10 OF 27
NEW ENGLAND DIVISION COMPUTED BY MM DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

BREACH ANALYSIS

DOWNSTREAM FAILURE HAZARD-

BREACH OUTFLOW $Q_b = \frac{8}{27} W_b \sqrt{g} y_o^{3/2}$ BASED ON CORPS
OF ENGINEERS "RULE 27 OF THUMB" GUIDANCE FOR
ESTIMATING D/S DAM FAILURE HYDROGRAPHS.

$W_b = 40\%$ OF MID-HEIGHT LENGTH OF THE DAM.
MID-HEIGHT LENGTH OF THE DAM IS ESTIMATED = 600 FT.
BASED ON FIELD INFORMATION

$$\therefore W_b = 0.4 \times 600 \\ = \underline{240 \text{ FT.}}$$

ASSUMED WATER DEPTH AT TIME OF FAILURE $y_o = \underline{7.7 \text{ FT.}}$
WITH FOUL AT TOP OF DAM (EL. 384.7)

$$Q_b = \frac{8}{27} \times 240 \times \sqrt{32.2} \times (7.7)^{3/2} = 8620 \text{ CFS}$$

PEAK FAILURE OUTFLOW $Q_p = Q_b + \text{SPILLWAY DISCHARGE}$
 $= 8620 + 525 = 9145 \text{ CFS}$
SAY = 9200 CFS

ESTIMATED FAILURE FLOOD DEPTH IMMEDIATELY D/S
FROM DAM $= 0.44 y_o$
 $= \underline{3.5 \text{ FT}}$

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 11 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

PERFORM DIS ROUTING OF PEAK FAILURE OUTFLOW
 SELECT A SECTION AA 200' DIS OF THE DAM
 USING MANNING'S EQUATION

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

$$= 2.5 \times A \times R^{2/3}$$

$n = 0.06$ ASSUMED
 (FAIRLY FLAT)
 $S = 0.01$ ESTIMATED FROM
 USGS MAP

ELVN	A SQ. FT.	P	R = A/P	R ^{2/3}	Q CFS
376	0	—	—	—	—
378	175	175	1	1	450
380	1000	650	1.54	1.33	3325
381	1481	696	2.13	1.65	6100
382	1995	735	2.71	1.94	9675

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED
 FOR SECTION AA

FOR PEAK FAILURE OUTFLOW $Q_1 = 9,200$ CFS, ELVN = 381.9 FROM
 STAGE DISCHARGE CURVE, AND STAGE AREA CURVE GIVES AREA
 = 1943 SQ. FT.

$$VOLUME OF REACH $V_1 = \frac{400 \times 1943}{43.560} \approx 17$ AC. FT.$$

THE SECTION AT AA IS ASSUMED TO BE UNIFORM BETWEEN THE DAM & RESERVOIR ROAD (400')

$$TRIAL $Q_2 = Q_1 \left(1 - \frac{V_1}{64}\right)$, WHERE $S =$ TOTAL STORAGE TO TOP OF DAM = 64 AC. FT.
 $= 9,200 \left(1 - \frac{17}{64}\right) \approx 6,750$ CFS.$$

FOR THIS Q_2 THE STAGE DISCHARGE CURVE GIVES ELVN = 381.25
 AND AREA = 1570 SQ. FT.

$$V_2 = \frac{400 \times 1570}{43.560} \approx 14$$
 AC. FT.


$$RECOMPUTING $Q_2 = 9,200 \left(1 - \frac{17+14}{64}\right) \approx 7,000$ CFS$$

AND FLOOD STAGE AT SECTION AA = 381.4

FLOOD DEPTH AT SECTION AA = 381.4 - 376 = 5.4 FT.

$$AND VELOCITY AT SECTION AA = \frac{7000}{1675} = 4.2$$
 FPS

D-12



SH 57112 SF 27
 1/1/80
 7/1/80

D-13

ELEVATION IN FEET

390

385

380

375

0

2000

4000

6000

8000


10000

DISCHARGE IN CFS

FARMINGTON RESERVOIR DAM

SECTION AA

SHEET 13 OF 27
 NR 7/11/80
 CB 7/1/80



PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 14 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

SELECTING A SECTION BB IMMEDIATELY D/S OF RESERVOIR ROAD

THIS COMPUTATION IS MADE TO ESTIMATE THE DEPTH OF
FLOOD WATER IN THE VICINITY OF A HOUSE LOCATED
ADJACENT TO THE STREAM.

USING MANNING'S EQUATION -

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

$n = 0.07$ ASSUMED
 $S = 0.08$ ESTIMATED
FROM USGS MAP

$$A = 11.25 H^2$$

$$P = 22.5 H$$

$$R = \frac{A}{P} = \frac{11.25 H^2}{22.5 H} = 0.5 H$$

FOR TOTAL PEAK FAILURE OUTFLOW OF 7,000 CFS

$$7,000 = \frac{1.486}{0.07} \times 11.25 H^2 \times (0.5 H)^{2/3} \times (0.08)^{1/2}$$

$$\therefore H = \underline{6.8 \text{ FT.}}$$

FLOOD STAGE = 376.8 (CHANNEL BED = EL. 370)

$$\text{AND VELOCITY} = \frac{7000}{527} = 13 \text{ FPS}$$

HENCE, THE HOUSE WOULD NOT BE IMPACTED SINCE
IT IS LOCATED APPROXIMATELY 10 FT ABOVE
STREAM BED.

D-15

ELEVATION IN FEET

380

370

100

100

200

HORIZONTAL DISTANCE IN FEET

FARMINGTON RESERVOIR DAM

STAGE AREA CURVE

175 FT D/S OF SECTION AA

SECTION BB

93
NA
7/17/80
7/18/80

SHEET 15 OF 27

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 16 OF 27
NEW ENGLAND DIVISION COMPUTED BY DWA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY Sh DATE 7/18/80

SELECTING A SECTION DD 1450' DIS OF SECTION BB
 (500 FT DIS OF SECTION CC AND JUST ABOVE DORSET LANE)
 BETWEEN SECTIONS BB AND CC THE STREAM IS NARROW WITH
 STEEP SLOPES (120' DROP IN LESS THAN 1000'); HENCE IT IS ASSUMED
 THAT THIS REACH WOULD NOT CONTRIBUTE TO ATTENUATION OF
 THE FLOOD VOLUME.

$$Q = 1.486 K A X R^{2/3} X S^{1/2} \quad m = 0.06 \text{ ASSUMED}$$

$$= 6.4 X A X R^{2/3} \quad A = 0.067 \text{ ESTIMATED FROM USGS MAP}$$

EL.	A SQ. FT.	P	R = A/P	R ^{2/3}	Q CFS
220	0	—	—	—	—
225	188	76	2.47	1.83	2,200
227	368	106	3.5	2.3	5,400
230	750	152	4.93	2.9	13,900

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED FOR SECTION DD.
 FOR PEAK FAILURE OUTFLOW $Q_{P1} = 7,000 \text{ CFS}$. ELVN = 227.5
 FROM STAGE DISCHARGE CURVE AND STAGE AREA CURVE
 GIVES AREA = 460 SQ. FT.

$$\text{VOLUME OF REACH } V_1 = \frac{500 \times 460}{43,560} \approx 5 \text{ AC. FT.}$$

$$\text{STORAGE REMAINING} = 64 - \frac{17+14}{2} \approx 4.9 \text{ AC. FT.}$$

$$\text{TRIAL } Q_{P2} = Q_{P1} \left(1 - \frac{V_1}{S}\right) = 7000 \left(1 - \frac{5}{49}\right) = 6,300 \text{ CFS}$$

FOR THIS Q_{P2} , ELVN = 227.5 AND AREA = 424 SQ. FT.

$$V_2 = \frac{500 \times 424}{43,560} \approx 5 \text{ AC. FT.}$$

$$Q_{P2} = 6,300 \text{ CFS}$$


AND FLOOD STAGE AT SECTION DD = 227.5

$$\text{FLOOD DEPTH AT SECTION DD} = 227.5 - 220 = 7.5 \text{ FT}$$

$$\text{AND VELOCITY AT SECTION DD} = \frac{6,300}{424} \approx 15 \text{ FPS}$$


THE DISCHARGE CAPACITY OF THE 4.5' DIA
 CULVERT = 170 CFS

FOR HW = 1.6 PER BUREAU OF PUBLIC
 ROADS. SCALE 2. MAY 1964.




100-10-10-10-10

D-17



SHEET 17 OF 27
DATE 7/11/80
CB 7/16/80



93
7/18/80
MA
7/18/80
SHEET 18 OF 27

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 19 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

SELECTING A SECTION EE 300 FT DIS OF SECTION DD
(BELOW DORSET LANE)

$$Q = 1.486 \times A \times R^{2/3} \times S^{1/2}$$

$$= 4.5 \times A \times R^{2/3}$$

$n = 0.06$ ASSUMED

$n = 0.033$ ESTIMATED FROM USGS MAP

EL.	AREA FT.	P	$R = A/P$	$R^{2/3}$	Q CFS
207	0	-	-	-	-
210	300	200	1.5	1.3	1750
211	517	234	2.21	1.7	3950
212	765	265	2.9	2	6900

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED
FOR SECTION EE.

FOR PEAK FAILURE OUTFLOW $Q_P = 6,300$ CFS, ELVN = 211.9
AND AREA = 739 SQ. FT.

$$VOLUME OF REACH $V_1 = \frac{300 \times 739}{43.560} \approx 5.4$ AC. FT.$$

$$STORAGE REMAINING = 49 - \frac{5.4}{2} = 44$$
 AC. FT.

$$TRIAL $Q_{P2} = Q_{P1} \left(1 - \frac{V_1}{S}\right) = 6,300 \left(1 - \frac{5.4}{44}\right) \approx 5,600$ CFS$$

FOR THIS Q_{P2} , ELVN = 211.6 AND AREA = 662 SQ. FT.


$$V_2 = \frac{300 \times 662}{43.560} = 4.6$$
 AC. FT.

$$RECOMPUTING $Q_{P2} = 6,300 \left(1 - \frac{5.4 + 4.6}{2}\right) \approx 5,600$ CFS$$

AND FLOOD STAGE AT SECTION EE = 211.6

$$FLOOD DEPTH AT SECTION EE = 211.6 - 207 = 4.6$$
 FT

$$AND VELOCITY AT SECTION EE = \frac{5,600}{662} = 8.5$$
 FPS



SHEET 20 OF 27
 DATE 7/17/80
 7/18/80

D-21

ELEVATION IN FEET

210

215

210

205

2000

4000

6000

8000

DISCHARGE IN CFS


FARMINGTON RESERVOIR DAM

SECTION EE

96 7/14/80

MS 7/11/80

SHEET 21 OF 27



PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 22 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

SELECTING A SECTION FF 250 FT DIS OF SECTION EE
(JUST ABOVE THE POND)

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times V^{1/2} \quad n = 0.06 \text{ ASSUMED}$$

$$= 3 \times A \times R^{2/3} \quad \Delta = 0.015 \text{ ESTIMATED FROM USGS MAP.}$$

EL	A, SQ. FT.	P	R = A/P	R ^{2/3}	Q CFS
198	0	—	—	—	—
200	250	250	1	1	750
201	532	315	1.7	1.42	2,300
203	1308	455	2.9	2	7,850

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED FOR SECTION FF.

FOR PEAK FAILURE OUTFLOW $Q_{P1} = 5600 \text{ CFS}$, $ELVN = 202.5$
 AND AREA = 1088 SQ. FT.

$$\text{VOLUME OF REACH } V_1 = \frac{250 \times 1088}{43.560} \approx 6 \text{ AC. FT.}$$

$$\text{STORAGE REMAINING} = 44 - \frac{6 + 4.6}{2} \approx 39 \text{ AC. FT.}$$

$$\text{TRIAL } Q_{P2} = Q_{P1} \left(1 - \frac{V_1}{S}\right) = 5,600 \left(1 - \frac{6}{39}\right) = 4,700 \text{ CFS}$$

FOR THIS Q_{P2} , $ELVN = 202.12$ AND AREA = 940 SQ. FT.

$$\therefore V_2 = \frac{250 \times 940}{43.560} \approx 5.5 \text{ AC. FT.}$$

$$\text{RECOMPUTING } Q_{P2} = 5,600 \left(1 - \frac{6 + 5.5}{39}\right) = 4,800 \text{ CFS}$$

$$\text{AND FLOOD STAGE AT SECTION FF} = 202.2$$

$$\text{FLOOD DEPTH AT SECTION FF} = 202.2 - 198 = 4.2 \text{ FT.}$$

$$\text{AND VELOCITY AT SECTION FF} = \frac{4,800}{965} = 5 \text{ FPS}$$

D-23

ELEVATION IN FEET

210
205
200
195

100 0 100 200 300 400 500 600 700 800 900


HORIZONTAL DISTANCE IN FEET
LOOKING DOWNSTREAM

FARMINGTON RESERVOIR DAM
STAGE AREA CURVE
250 FT DIS OF SECTION EE

SECTION EE

SHEET 23 OF 27
NW 7/11/80
DB 7/12/80

D-24



SHEET 24 OF 27
 MAY 11/11/80
 CB 7/15/80

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 25 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

FAILURE HAZARD POTENTIAL SUMMARY OF BREACH ANALYSIS RESULTS:

LOCATION	DISTANCE FROM DAM FT.	PEAK FLOW RATE CFS	FLOOD STAGE	FLOOD DEPTH FT.	VELOCITY FPS	STORAGE VOLUME REMAINING AC-FT
DAM	0	9200	380.5	3.5	—	64
AA	200	7000	381.4	5.4	4.2	49
BB	375	7000	376.8	6.8	13	49
DD	1825	6300	227.5	7.5	15	44
EE	2125	5600	211.6	4.6	8.5	39
FF	2375	4800	202.2	4.2	5	33

BETWEEN THE DAM AND RESERVOIR ROAD, SOME FAIRLY FLAT LAND EXISTS AND SECTION AA IS TAKEN THROUGH THIS AREA ADJACENT TO THE FILTER BEDS. THIS AREA ATTENUATES $15 \pm$ AC-FT, WHICH IS EQUIVALENT TO 23% OF THE TOTAL BREACH VOLUME OF 64 AC-FT. THE RESERVOIR ROAD WOULD BE INUNDATED AND THE CULVERT ON THIS ROAD WOULD BE DAMAGED.

AT SECTION DD TAKEN ABOVE DORSET LANE, THE FLOOD DEPTH IS ESTIMATED TO BE 7.5' WITH A HIGH VELOCITY OF 15 FPS. AT LEAST ONE HOUSE, LOCATED ON THE RIGHT BANK OF THE STREAM WITH ITS 1ST FLOOR ONLY $4 \pm$ FT. ABOVE THE STREAM BED WOULD BE FLOODED WITH $3.5 \pm$ FT. OF WATER. THE CULVERT ON DORSET LANE IS ESTIMATED TO HAVE A CAPACITY OF 1700 CFS WHEN COMPARED WITH 6300 CFS OF PEAK FLOW. THUS, THE CULVERT WOULD BE DAMAGED AND THE ROAD WOULD BE INUNDATED. THIS WOULD CUT OFF ACCESS TO SEVERAL HOUSES ON THE LOOP OF DORSET LANE. FURTHER,

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 26 OF 27
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/17/80
FARMINGTON RES. DAM CHECKED BY EB DATE 7/18/80

ASSUMING THAT THE CULVERT STAYS, THE FLOOD WATER WOULD RISE, THUS IMPACTING OTHER HOUSES IN THE VICINITY.

FURTHER D/S AT SECTION FF, THE FLOOD STAGE IS ESTIMATED TO BE 202.2, FLOODING AT LEAST ONE HOUSE WITH 5 \pm FT. OF WATER. THIS HOUSE IS 4 \pm FT. ABOVE THE W.S. ELEVATION (EL. 193) OF THE SMALL POND LOCATED JUST D/S OF SECTION FF.

IN THE ENTIRE REACH, BETWEEN THE DAM AND SECTION FF, ONLY 48% OF DAM FAILURE FLOOD VOLUME IS EXPECTED TO BE ATTENUATED AND 33 AC.FT. STILL REMAINS.

THUS, WITH AT LEAST TWO HOUSES FLOODED WITH 3.5 FT TO 5 FT OF WATER, TWO CULVERTS DAMAGED, TWO ROADS INUNDATED AND A POTENTIAL FOR FLOODING ADDITIONAL HOUSES ON DORSET LANE, WITH A POSSIBLE LOSS OF LIVES OF MORE THAN A FEW, A HIGH HAZARD POTENTIAL IS CONSIDERED LIKELY.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-18 SHEET 27 OF 27
NEW ENGLAND DIVISION COMPUTED BY MWA DATE 7/19/80
FARMINGTON RES. DAM CHECKED BY Eb DATE 7/19/80
REVISED 9/12/80

SUMMARY- HYDRAULIC/HYDROLOGIC COMPUTATIONS

TEST FLOOD PEAK INFLOW $\frac{1}{2}$ PMF 315 CFS

(PARALLEL COMPUTATIONS HAVE BEEN MADE FOR PMF
PEAK INFLOW AND RESULTS ARE SUMMARIZED BELOW)

PERFORMANCE AT PEAK FLOOD CONDITIONS:

	PMF	$\frac{1}{2}$ PMF
PEAK INFLOW CFS	625	315
PEAK OUTFLOW CFS	525	250
SPILL. CAP. TO TOP OF DAM CFS	525	525
SPILL. CAP. TO TOP OF DAM % OF PEAK OUTFLOW	100	210
SPILL. CAP. TO PEAK FLOOD ELVN. CFS	525	250
SPILL. CAP. TO PEAK FLOOD ELVN. % OF PEAK OUTFLOW	100	100

PERFORMANCE:

MAXIMUM POOL ELVN NGVD	384.7	383.65
MAX. SURCHARGE HEIGHT ABOVE SPILL. CREST FT.	2.7	1.65
NON- OVERFLOW SECTION OF THE DAM OVERTOPPED	NO	NO

DOWNSTREAM FAILURE CONDITIONS:

PEAK FAILURE OUTFLOW CFS	9200
FLOOD DEPTH IMMEDIATELY D/S FROM DAM	3.5 FT
CONDITIONS AT INITIAL IMPACT AREA: SECTION DD (STREAM BED EL. 220)	
ESTIMATED STAGE BEFORE FAILURE WITH 250 CFS	222.6 NGVD
ESTIMATED STAGE AFTER FAILURE WITH 6300 CFS	227.5 NGVD
ESTIMATED RAISE IN STAGE AFTER FAILURE ΔY_1	4.9 FT
CONDITIONS AT SECONDARY IMPACT AREA: SECTION FF (STREAM BED EL. 198)	
ESTIMATED STAGE BEFORE FAILURE WITH 250 CFS	199.3 NGVD
ESTIMATED STAGE AFTER FAILURE WITH 4800 CFS	202.2 NGVD
ESTIMATED RAISE IN STAGE AFTER FAILURE ΔY_2	2.9 FT

PRELIMINARY GUIDANCE
FOR ESTIMATING
MAXIMUM PROBABLE DISCHARGES
IN
PHASE I DAM SAFETY
INVESTIGATIONS

New England Division
Corps of Engineers

March 1978


MAXIMUM PROBABLE FLOOD INFLOWS
NED RESERVOIRS

<u>Project</u>	<u>Q</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> cfs/sq. mi.
1. Hall Meadow Brook	26,600	17.2	1,546
2. East Branch	15,500	9.25	1,675
3. Thomaston	158,000	97.2	1,625
4. Northfield Brook	9,000	5.7	1,580
5. Black Rock	35,000	20.4	1,715
6. Hancock Brook	20,700	12.0	1,725
7. Hop Brook	26,400	16.4	1,610
8. Tully	47,000	50.0	940
9. Barre Falls	61,000	55.0	1,109
10. Conant Brook	11,900	7.8	1,525
11. Knightville	160,000	162.0	987
12. Littleville	98,000	52.3	1,870
13. Colebrook River	165,000	118.0	1,400
14. Mad River	30,000	18.2	1,650
15. Sucker Brook	6,500	3.43	1,895
16. Union Village	110,000	126.0	873
17. North Hartland	199,000	220.0	904
18. North Springfield	157,000	158.0	994
19. Ball Mountain	190,000	172.0	1,105
20. Townshend	228,000	106.0(278 total)	820
21. Surry Mountain	63,000	100.0	630
22. Otter Brook	45,000	47.0	957
23. Birch Hill	88,500	175.0	505
24. East Brimfield	73,900	67.5	1,095
25. Westville	38,400	99.5(32 net)	1,200
26. West Thompson	85,000	173.5(74 net)	1,150
27. Hodges Village	35,600	31.1	1,145
28. Buffumville	36,500	26.5	1,377
29. Mansfield Hollow	125,000	159.0	786
30. West Hill	26,000	28.0	928
31. Franklin Falls	210,000	1000.0	210
32. Blackwater	66,500	128.0	520
33. Hopkinton	135,000	426.0	316
34. Everett	68,000	64.0	1,062
35. MacDowell	36,300	44.0	825

MAXIMUM PROBABLE FLOWS
BASED ON TWICE THE
STANDARD PROJECT FLOOD
(Flat and Coastal Areas)

<u>River</u>	<u>SPF</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> (cfs/sq. mi.)
1. Pawtuxet River	19,000	200	190
2. Mill River (R.I.)	8,500	34	500
3. Peters River (R.I.)	3,200	13	490
4. Kettle Brook	8,000	30	530
5. Sudbury River.	11,700	86	270
6. Indian Brook (Hopk.)	1,000	5.9	340
7. Charles River.	6,000	184	65
8. Blackstone River.	43,000	416	200
9. Quinebaug River	55,000	331	330

ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow (Q_{p1}) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " Q_{p1} ".

b. Determine Volume of Surcharge ($STOR_1$) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:


$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$

STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " Q_{p2} "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " Q_{p3} ".

MAXIMUM PROBABLE FLOOD PEAK FLOW RATES

x5 - NED DAM IDENTIFICATION
 ⊗ 7' - TWICE SPF AT INDICATED SITES
 DEC. 1977



SURCHARGE STORAGE ROUTING SUPPLEMENT

**STEP 3: a. Determine Surcharge Height and
"STOR₂" To Pass "Q_{p2}"**

**b. Avg "STOR₁" and "STOR₂" and
Compute "Q_{p3}".**

**c. If Surcharge Height for Q_{p3} and
"STOR_{AVG}" agree O.K. If Not:**

**STEP 4: a. Determine Surcharge Height and
"STOR₃" To Pass "Q_{p3}"**

**b. Avg. "Old STOR_{AVG}" and "STOR₃"
and Compute "Q_{p4}"**

**c. Surcharge Height for Q_{p4} and
"New STOR_{AVG}" should Agree
closely**

SURCHARGE STORAGE ROUTING ALTERNATE

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{\text{STOR}}{19} \right)$$


$$Q_{p2} = Q_{p1} - Q_{p1} \left(\frac{\text{STOR}}{19} \right)$$

FOR KNOWN Q_{p1} AND 19" R.O.


Q_{p2}
=====

STOR
=====

EL.
=====



"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_0 = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS 1/2 OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING Q_{p2} (TRIAL).

D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

APPENDIX E

**INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS**

NOT AVAILABLE AT THIS TIME